

Presented to:

**Boston Redevelopment
Authority**



Report for:

**Engineering Design Services for
Environmental Remediation and
Building Demolition at Dudley Square**

**Geotechnical Data Report
Roxbury, MA.**



In Reference to:

BRA Contract No. 5076

October 2007



Submitted by:

Jacobs Engineering Group Inc.

Two Center Plaza
Boston, Massachusetts 02108

Geotechnical Data Report

Engineering Design Services for Environmental
Remediation and Site Clearance at Dudley Square

Roxbury, Massachusetts

October 2007

Prepared for:



Boston Redevelopment
Authority
22 Drydock
Avenue
Boston, Massachusetts
02210

Prepared by:

JACOBS

Jacobs Engineering Group Inc.
Two Center Plaza
Boston, Massachusetts 02108

Table of Contents

	PAGE
INTRODUCTION	1
PROJECT INFORMATION	1
SCOPE OF WORK	1
GEOTECHNICAL INVESTIGATION	2
SUBSURFACE CONDITIONS	2
LABORATORY TESTING	3
FOUNDATION RECOMMENDATIONS	4

FIGURES

FIGURE 1 – Locus Map

FIGURE 2 – Boring Location Plan

FIGURE 3 – As-Built Boring Location Survey Plan

FIGURE 4 – Plan and Soil Profile Cross-Section A-A

FIGURE 5 – Plan and Soil Profile Cross-Section B-B

ATTACHMENTS

ATTACHMENT A – Boring Logs and Test Pit Logs

ATTACHMENT B – Lab Results

ATTACHMENT C – Photographs

INTRODUCTION

This geotechnical report presents the procedures and the results of the subsurface investigation performed at the Dudley Square "Ferdinand Building" project site. The general location of the site is shown in Figure 1, the Locus Map. The results of the subsurface investigation are provided to support (1) the bracing design to salvage the Ferdinand Building's façade, (2) building demolition, and (3) future design and construction work at the project site.

Four test borings were drilled and four test pits were excavated as part of the field investigation. Three of the borings were drilled on the paved sidewalk adjacent to the building; the fourth boring was drilled in the vacant lot at the rear of the building. The test pits were excavated to expose the building foundation. Two of the test pits were excavated from inside the basement of the building to expose the bottom of the building foundation from the interior. The other two test pits were excavated at the outside rear of the building.

PROJECT INFORMATION

The City of Boston, through the Boston Redevelopment Authority (BRA), plans to construct a new office building at the location of the Ferdinand Building. The BRA plans to demolish the interior and rear portions of the Ferdinand Building and to salvage the façade at the front corner and two sides of the building for incorporation it into the new office building. The building façade will be braced and supported in place while the interior and rear portions of the building are demolished.

The work being performed under this Contract is obtaining information relating to the existing building foundation and subsurface conditions at the project site as necessary to support (1) building demolition design (2) design of the bracing and salvage system for the façade.

SCOPE OF WORK

This report has been prepared by Jacobs in accordance with the scope of work for the contract between Jacobs and BRA for the Dudley Square project.

This report does not address the environmental characterization of soils at the site. These issues will be addressed at a later stage of project development. If waste soils are generated during future site activities these soils will need to be environmentally characterized to determine the presence of oil and/or hazardous materials in accordance with applicable requirements of 310 CMR 40.000 Massachusetts Contingency Plan.

GEOTECHNICAL INVESTIGATION

Jacobs planned a subsurface investigation program and hired a drilling contractor, New Hampshire Boring Company, to drill four borings and excavate four test pits at the project site. The borings were drilled using a CME-50T drill-rig between June 28 and July 13, 2007. A boring location plan is included as Figure 2. The borings were advanced by wash boring with casing techniques to refusal. After refusal rock coring was employed. Standard penetration tests (SPT) with split spoon sampling were typically performed at five-foot intervals of depth to establish the density or consistency of in-situ soils and to obtain soil samples in accordance with ASTM D-1586 "Standard Test Method for Penetration Test and Split-Barrel Sampling of Soils. Small representative samples were obtained during these tests and were used to classify the soils encountered.

Within the clay stratum, undisturbed samples were obtained using a thin wall sampler (Shelby tube) in accordance with ASTM D-1587 "Standard Practice for Thin-Walled Tube Sampling of Soils for Geotechnical Purposes.

The bedrock was cored to obtain rock samples. Core runs were generally 5 ft in length. Cores were placed in wooden core boxes for transport and storage by the drilling contractor for later laboratory testing and future examination. The core boxes and the rock core samples will be stored by the drilling contractor (New Hampshire Boring) for two years.

The subsurface conditions encountered at the boring locations are shown on the test boring logs in Attachment A. These test boring logs represent our interpretation of the subsurface conditions based on visual examination of field samples and laboratory test completed on the field obtained samples. Any use of this information is the responsibility of the user. The lines designating the interfaces between the various strata on the boring logs represent the approximate interface locations. Water levels shown on the boring logs represent the conditions only at the time the measurements were made. The as-built boring and test pit locations and elevations were surveyed by Nitsch Engineering on July 23, 2007. The survey results are shown in Figure 3.

SUBSURFACE CONDITIONS

The soil test borings reveal a soil profile consisting of successive layers of Fill, Sand/Silty-Sand, Clay, Glacial Till, and Bedrock. Each of the strata is briefly discussed in the paragraphs that follow:

Stratum I "Fill" consist of man made Fill with materials that include sand, silt, gravel, asphalt, bricks, boulders, and miscellaneous construction debris. The

thickness of the Fill varies from 11-ft to 25-ft from the ground surface. Standard penetration test (SPT) resistances in Stratum I ranged widely from 8 to over 90 blows per foot.

Stratum II "Sand/Silt" is predominantly Sand, Silt, some Gravel and occasional thin lenses of Clay. The Clay was only encountered in Boring B4. The thickness of the Sand and Silt stratum varies from 15-ft to 35-ft. SPT resistances ranged from 10 to over 70 blows per foot.

Stratum III "Clay" is predominantly Clay with thickness of about 8 to 15 ft. SPT resistances in the Clay stratum ranged from no resistance at all to the Weight of the Hammer to over 30 blows per foot.

Stratum IV "Glacial Till" is predominantly glacial till with a uniform thickness of about 15 to 20 ft across the borings. SPT resistances in the Till stratum ranged from 35 blows per foot to SPT refusal.

The top of bedrock ranges from 60-ft to 80-ft below ground surface. At three of the boring locations, conglomerate type sedimentary rocks consisting of pebbles and consolidated gravel was encountered. Argillaceous sedimentary rock composed mainly of clay particles was encountered at the fourth boring location.

The driller experienced some difficulty driving the casing through obstructions in the fill stratum while installing the three borings on the paved sidewalk. These obstructions are assumed to be boulders and building materials such as granite blocks. On two occasions, the casing were so badly damaged that the driller had to extract the casing and replace the lead casing as the split-spoon could not be advanced through the damaged casing.

The groundwater depth varied from 13-ft to 17-ft below the ground surface.

LABORATORY TESTING

The scheduled laboratory tests were conducted in accordance with ASTM Specifications by GeoTesting Express of Boxborough, Massachusetts to determine the physical and engineering characteristics of selected split-spoon samples. Details of laboratory testing and test results are presented in Attachment 2.

Environmental field screening and laboratory analysis of soil samples to determine the presence of oil and/or hazardous materials were not completed at this time. Environmental investigations have been completed by previously completed by others to address oil and/or hazardous materials per 310 CMR 40.000 the Massachusetts Contingency Plan.

FOUNDATION RECOMMENDATIONS

We understand that a future 10- to 14-story office building is planned for the site. The alluvial sand and silt layer underlying the fill layer is suitable for supporting the proposed building. Based on the anticipated building load, individual footings designed with a low enough bearing pressure to avoid overstressing the subgrade soils would occupy a large proportion of the foundation area. Therefore a mat foundation will be more economical and is recommended for the building. In addition, a mat foundation will distribute column and wall loads more evenly to the underlying soils and thus reduce differential settlements, especially with the potential for loose soil pockets existing within the subgrade.

The mat foundation should be supported on the sand/silt stratum with a maximum bearing pressure of 2 tons per square foot (tsf). We estimate the maximum mat settlement of 2 inches under this bearing pressure, to produce a tolerable differential settlement of $\frac{3}{4}$ inches or less between adjacent columns. We anticipate that over half of these settlements will occur during construction as the building loads are added. The perimeter of the mat should be founded at least 4 feet below finished exterior grade for frost protection.

For subsurface building basement with lower foundation elevation, some of the compressible sand/silt stratum would be removed (i.e. less sand/silt settlement), but the bearing surface would now be that much closer to the clay stratum (i.e. more clay settlement). Therefore for preliminary design purpose, the same maximum bearing pressure of 2 tsf should be used regardless of basement depth.

For the final design, we recommend additional subsurface investigation and testing be conducted for the remaining site to confirm the subsurface condition, and to estimate the final design parameters such as the mat subgrade reaction modulus. The net stress increase from the proposed building and its impact or resulting settlement on the existing nearby buildings should be evaluated. The liquefaction susceptibility of the soils at the site during a seismic event should also be investigated.

Laboratory Test Result Summary
Table - 1

Boring and Sample ID	Depth (ft)	Sample Type	Soil Description	Soil Class	% Retained No. 4 Sieve	% Finer No. 200 Sieve	Moist Content (%)	Atterberg Limits			
								Liquid Limit (LL)	Plastic Limit (PL)	Plastic Index (PI)	Liquidity Index (LI)
JE-B1 - S-7	30-31.5	Jar	Fine Sand		0	7					
JE-B2 - S-14	62-64	Jar	Silty gravel and sand		6	28					
JE-B3 - ST1	66-68	Shelby Tube	Greenish gray clay	CL	0	96	38	43	17	26	1
JE-B4 - ST1	62-64	Shelby Tube	Greenish gray clay	CL	0	100	35	52	22	30	0
JE-B4 - S-15	75-76.5	Jar	Olive clay		0	100					

Bulk density and compressive strenght of rock core specimen by ASTM D 2938

Boring and Sample ID	Depth (ft)	Bulk Density,	Compressive Strength, (psi)	Comment
JE-B1 - RC-1	64-69	162	2,705	


Figure 1
Locus Map



FIGURE 1 - Locus Map

Figure 2
Boring Location Map

Figure 3
As-Built Boring Location Survey Plan



LEGEND:

- | | |
|----------------------|-------------------------------|
| · MBTA MANHOLE | · DECIDUOUS TREE |
| · SEWER MANHOLE | · NOW OR FORMERLY |
| · DRAIN MANHOLE | · TEMPORARY BENCH MARK |
| · TELEPHONE MANHOLE | · TT - TOP OF TRAP |
| · ELECTRIC MANHOLE | · N.V.P. - NO VISIBLE PIPES |
| · WATER MANHOLE | · BH - BUILDING HEIGHT |
| · MANHOLE | · FPA - FOOTPRINT AREA |
| · HANDICAP RAMP | · T - TOP |
| · GAS SHUT OFF | · B - BOTTOM |
| · WATER SHUT OFF | · BIT. - BITUMINOUS |
| · BOSTON WATER VALVE | · CONC. - CONCRETE |
| · CATCH BASIN | · VGC - VERTICAL GRANITE CURB |
| · LIGHT POLE | · CLF - CHAIN LINK FENCE |
| · HYDRANT | · MF - METAL FENCE |
| · SIGN | · X - FENCE |
| · TRAFFIC SIGNAL | · S - SEWER |
| · ELECTRIC HANDHOLE | · D - DRAIN |
| · GATE POST | · CS - COMBINED SEWER |
| · FIRE ALARM | · W - WATER |
| · INVERT ELEVATION | · G - GAS |
| · RIM ELEVATION | · E - ELECTRIC |
| · SHUT OFF | · M - MBTA |
| · BORING | · T - TELEPHONE |
| · TEST PIT | |

NOTES:

1. EXISTING CONDITIONS FROM PLAN PREPARED BY HARRY R. FELDMAN, INC. ENTITLED "ALTA/ACSM LAND TITLE SURVEY AND EXISTING CONDITIONS PLAN, DUDLEY SQUARE, BOSTON (ROXBURY DISTRICT), MASS" SCALE: 1"=20', DATED APRIL 28, 2005.
2. ELEVATIONS REFER TO BOSTON CITY BASE (BCB).



www.nitecheng.com
186 Lincoln Street, Suite 200
Boston, MA 02111-2403
T: (617) 338-0063
F: (617) 338-6472

BORING LOCATION PLAN
ORDINAND BUILDING
BOSTON (ROXBURY), MASSACHUSETTS
 PREPARED FOR:
ENGINEERING GROUP, INC.
 BOSTON, MASSACHUSETTS 02108


SHEET:
EX-1
 OF 1 REV.

Attachment A

Boring Logs and Test Pit Logs

Figure 4

Plan and Soil Profile Cross-Section A-A



BOSTON REDEVELOPMENT AUTHORITY
 DUDLEY SQUARE DEMOLITION PROJECT
 ROXBURY, MASSACHUSETTS
 E2X26200

Jacobs Civil Inc.

SUBSURFACE PROFILE
 SECTION A - A
 FIGURE 4B


Figure 5

Plan and Soil Profile Cross-Section B-B

 BORING

PLAN
SECTION B-B
FIGURE 5A

CROSS SECTION B-B
SCALE: 1" = 20'-0"



BOSTON REDEVELOPMENT AUTHORITY
DUDLEY SQUARE DEMOLITION PROJECT
ROXBURY, MASSACHUSETTS
E2X26200

JE[®] JACOBS

SUBSURFACE PROFILE
SECTION B - B
FIGURE 5B

JE JACOBS

PROJECT	DUDLEY SQUARE DEMOLITION PROJECT				BORING NO.	JE-B1		
LOCATION	2262 Washington Street							
OWNER	BOSTON REDEVELOPMENT AUTHORITY					SHEET 1 OF 2		
JOB NUMBER	E2X26200							
CONTRACTOR	NH Boring Inc		DRILLER	B. Thompson	ELEVATION	19.9		
GROUNDWATER READINGS			DRILL RIG	CME-50T	DATUM	FT MSL		
DATE/TIME	DEPTH(ft)	REMARKS	SPT HAMMER	140 lb Auto	GRID	N	4859.0163	
7/13/2007	13	24 hour Reading			COORD	E	5080.3991	
					DATE START	7/12/07		
					DATE END	7/13/07		

Page 1: 0-35 feet. Each subsequent page displays 40 feet.

COHESIVE SOIL		NON-COHESIVE SOIL		RELATIVE PROPORTIONS OF SOIL COMPONENTS		LEGEND					
BLOWS/FT	CONSISTENCY	BLOWS/FT	DENSITY			 Auger Sample (AS)	 Rock Core (RC) and RQD (%)	 Split-Spoon Sample (SS) and Blow Counts per 6" REC (in)	 Undisturbed (UJ-Shelby Tube, (P)-Piston	 Jar Sample (JS)	 Bag Sample (B)
0 - 2	VERY SOFT	0 - 4	VERY LOOSE	< 10%	TRACE	REFER TO THE SHEET ENTITLED "KEY TO DESCRIPTION AND CLASSIFICATION OF SUBSURFACE MATERIALS" FOR ADDITIONAL SYMBOLOGY.				BORING NO.	JE-B1
3 - 4	SOFT	5 - 10	LOOSE	15 - 25%	LITTLE						
5 - 8	MEDIUM STIFF	11 - 30	MEDIUM DENSE	30 - 45%	SOME						
9 - 15	STIFF	31 - 50	DENSE	50 - 100%	MOSTLY						
16 - 30	VERY STIFF	51 +	VERY DENSE								
30 +	HARD										

LOG OF TEST BORING



PROJECT	DUDLEY SQUARE DEMOLITION PROJECT
LOCATION	2262 Washington Street
OWNER	BOSTON REDEVELOPMENT AUTHORITY
JOB NUMBER	E2X26200

BORING
NO.

JE-B1

SHEET 2 OF 2

DEPTH (ft)	STRATA SYMBOL	SAMPLE DATA	SAMPLE NO.	DEPTH (ft)	REC. (in)/(%)	ELEV.	FIELD CLASSIFICATION AND REMARKS
		2 2 4	S-8	35 - 36.5	18		CLAY, olive gray, soft
		WOH 2 3 3	S-9	37 - 39	24		SAME
40		3 3 8 8	S-10	39 - 41	24	-19.8	CLAY, olive green, mostly clay with sand (Top 8-inch = clay; Bottom 16-inch=clay with sand)
		7 8 14 55	S-11	41 - 43	24		Olive green SILTY SAND, medium dense, some medium gravel, top 2-inch is predominantly clay with sand
45		21 70 44 62	S-12	43 - 45	12		Rusty brown very dense GRAVEL, little freshly crushed rock fragments. Probable cobble. (TILL) (Wash boring to 50ft below ground surface.)
50		23 23 27	S-13	50 - 51.5	8		SAME
55		34 48 50	S-14	55 - 56.5	14		SAME
60		100/3"	S-15	60 - 60.25	3	-40.4	Light gray to brown GRAVEL with silty sand. (Refusal at 60-ft 3-in. Probable top of bedrock.)
65		RQD=20	RC-1	64 - 69	60		(Wash boring to 64' BGS) Brown, gray and black conglomerate SANDSTONE, highly fractured, severely weathered.
70						-49.1	Bottom of Hole at 69'.

Page 1: 0-35 feet. Each subsequent page displays 40 feet.

COHESIVE SOIL		NON-COHESIVE SOIL		RELATIVE PROPORTIONS OF SOIL COMPONENTS		LEGEND					
BLOWS/FT	CONSISTENCY	BLOWS/FT	DENSITY			 Auger Sample (AS)	 Rock Core (RC) and RQD (%)	 Split-Spoon Sample (SS) and Blow Counts per 6"	 Undisturbed (U)-Shelby Tube, (P)-Piston	 Jar Sample (JS)	 Bag Sample (B)
0 - 2	VERY SOFT	0 - 4	VERY LOOSE	< 10%	TRACE	REFER TO THE SHEET ENTITLED "KEY TO DESCRIPTION AND CLASSIFICATION OF SUBSURFACE MATERIALS" FOR ADDITIONAL SYMBOLOGY.				BORING NO.	JE-B1
3 - 4	SOFT	5 - 10	LOOSE	15 - 25%	LITTLE						
5 - 8	MEDIUM STIFF	11 - 30	MEDIUM DENSE	30 - 45%	SOME						
9 - 15	STIFF	31 - 50	DENSE	50 - 100%	MOSTLY						
16 - 30	VERY STIFF	51 +	VERY DENSE								
30 +	HARD										

REFER TO THE SHEET ENTITLED "KEY TO DESCRIPTION AND CLASSIFICATION OF SUBSURFACE MATERIALS" FOR ADDITIONAL SYMBOLOGY.

BORING
NO.

JE-B1

JE JACOBS

PROJECT		DUDLEY SQUARE DEMOLITION PROJECT			BORING NO.	JE-B2		
LOCATION		2262 Washington Street						
OWNER		BOSTON REDEVELOPMENT AUTHORITY				SHEET 1 OF 3		
JOB NUMBER		E2X26200						
CONTRACTOR		NH Boring Inc		DRILLER	B. Thompson	ELEVATION		28.1
GROUNDWATER READINGS				DRILL RIG	CME-50T	DATUM		FT MSL
DATE/TIME		DEPTH(ft)	REMARKS	SPT HAMMER	140 lb Auto	GRID	N	4940.9919
7/24/2007		16	24 hour reading			COORD	E	5135.3344
						DATE START		7/10/07
						DATE END		7/11/07

Page 1: 0-35 feet. Each subsequent page displays 40 feet.

COHESIVE SOIL		NON-COHESIVE SOIL		RELATIVE PROPORTIONS OF SOIL COMPONENTS		LEGEND					
BLOWS/FT	CONSISTENCY	BLOWS/FT	DENSITY			 Auger Sample (AS)	 Rock Core (RC) and RQD (%)	 Split-Spoon Sample (SS) and Blow Counts per 6" REC (in)	 Undisturbed (U)-Shelby Tube, (P)-Piston	 Jar Sample (JS)	 Bag Sample (B)
0 - 2	VERY SOFT	0 - 4	VERY LOOSE	< 10%	TRACE	REFER TO THE SHEET ENTITLED "KEY TO DESCRIPTION AND CLASSIFICATION OF SUBSURFACE MATERIALS" FOR ADDITIONAL SYMBOLOGY.					
3 - 4	SOFT	5 - 10	LOOSE	15 - 25%	LITTLE						
5 - 8	MEDIUM STIFF	11 - 30	MEDIUM DENSE	30 - 45%	SOME						
9 - 15	STIFF	31 - 50	DENSE	50 - 100%	MOSTLY						
16 - 30	VERY STIFF	51 +	VERY DENSE								
30 +	HARD					BORING NO.		JE-B2			

LOG OF TEST BORING



PROJECT	DUDLEY SQUARE DEMOLITION PROJECT
LOCATION	2262 Washington Street
OWNER	BOSTON REDEVELOPMENT AUTHORITY
JOB NUMBER	E2X26200

**BORING
NO.**

JE-B2

SHEET 2 OF 3

DEPTH (ft)	STRATA SYMBOL	SAMPLE DATA	SAMPLE NO.	DEPTH (ft)	REC. (in)/(%)	ELEV.	FIELD CLASSIFICATION AND REMARKS
		8 10 14	S-8	35 - 36.5	14		Rusty brown medium dense fine SAND, little silt
						-9.4	
40		8 10 15	S-9	40 - 41.5	15		Rusty brown medium dense silty fine SAND with occasional clumps of clay
45		9 17 13	S-10	45 - 46.5	16		SAME
						-19.9	
50		4 7 10	S-11	50 - 51.5	18		Brownish gray CLAY, stiff (Top 6-inches=silty sand)
55		9 7 6	S-12	55 - 56.5	18		SAME
60		WOH 5 13 14	S-13	60 - 62	24		Olive gray stiff CLAY with rusty brown medium gravel.
		7 56 24 47	S-14	62 - 64	24		Rusty brown GRAVEL and CLAY, top 8-inch=clay, bottom of spoon = Till
65		48 54 100/5"	S-15	65 - 66.4	9		Brown, GRAVEL with sand, clay and silt (TILL)
70		25 24 22	S-16	70 - 71.5	13		SAME

Page 1: 0-35 feet. Each subsequent page displays 40 feet.

COHESIVE SOIL		NON-COHESIVE SOIL		RELATIVE PROPORTIONS OF SOIL COMPONENTS		LEGEND					
BLOWS/FT	CONSISTENCY	BLOWS/FT	DENSITY			 Auger Sample (AS)	 Rock Core (RC) and RQD (%)	 Split-Spoon Sample (SS) and Blow Counts per 6" REC (in)	 Undisturbed (U)-Shelby Tube, (P)-Piston	 Jar Sample (JS)	 Bag Sample (B)
0 - 2	VERY SOFT	0 - 4	VERY LOOSE	< 10%	TRACE	REFER TO THE SHEET ENTITLED "KEY TO DESCRIPTION AND CLASSIFICATION OF SUBSURFACE MATERIALS" FOR ADDITIONAL SYMBOLOGY.				BORING NO.	JE-B2
3 - 4	SOFT	5 - 10	LOOSE	15 - 25%	LITTLE						
5 - 8	MEDIUM STIFF	11 - 30	MEDIUM DENSE	30 - 45%	SOME						
9 - 15	STIFF	31 - 50	DENSE	50 - 100%	MOSTLY						
16 - 30	VERY STIFF	51 +	VERY DENSE								
30 +	HARD										

REFER TO THE SHEET ENTITLED "KEY TO DESCRIPTION AND CLASSIFICATION OF SUBSURFACE MATERIALS" FOR ADDITIONAL SYMBOLOGY.

**BORING
NO.**

JE-B2

LOG OF TEST BORING

				PROJECT		DUDLEY SQUARE DEMOLITION PROJECT		BORING NO.	JE-B2
				LOCATION		2262 Washington Street			
				OWNER		BOSTON REDEVELOPMENT AUTHORITY			
				JOB NUMBER		E2X26200			
SHEET 3 OF 3									

DEPTH (ft)	STRATA SYMBOL	SAMPLE DATA	SAMPLE NO.	DEPTH (ft)	REC. (in)/(%)	ELEV.	FIELD CLASSIFICATION AND REMARKS
75		30 31 23	S-17	75 - 76.5	14		ARGILITE, gray, soft (probable decomposed cobble/boulder)
80		100/1" RQD=0	S-18 RC-1	80 - 80.1 80.1 - 85	1 36	-52.0	(Refusal at 80.33-ft Probable top of bedrock) ARGILITE, gray, soft severely weathered and decomposed
85		RQD=0	RC-2	85 - 90	36		SAME (Driller had difficulty extracting cored sample from the core barrel due to the soft nature of the rock)
90						-61.9	Bottom of Hole at 90'.
95							
100							
105							
110							

Page 1: 0-35 feet. Each subsequent page displays 40 feet.

COHESIVE SOIL		NON-COHESIVE SOIL		RELATIVE PROPORTIONS OF SOIL COMPONENTS		LEGEND					
BLOWS/FT	CONSISTENCY	BLOWS/FT	DENSITY								
0 - 2	VERY SOFT	0 - 4	VERY LOOSE	< 10%	TRACE	REFER TO THE SHEET ENTITLED "KEY TO DESCRIPTION AND CLASSIFICATION OF SUBSURFACE MATERIALS" FOR ADDITIONAL SYMBOLOGY.					
3 - 4	SOFT	5 - 10	LOOSE	15 - 25%	LITTLE						
5 - 8	MEDIUM STIFF	11 - 30	MEDIUM DENSE	30 - 45%	SOME						
9 - 15	STIFF	31 - 50	DENSE	50 - 100%	MOSTLY						
16 - 30	VERY STIFF	51 +	VERY DENSE								
30 +	HARD										

BORING NO.	JE-B2
------------	-------

LOG OF TEST BORING

		PROJECT	DUDLEY SQUARE DEMOLITION PROJECT				BORING NO.	JE-B3		
		LOCATION	2262 Washington Street							
		OWNER	BOSTON REDEVELOPMENT AUTHORITY							
		JOB NUMBER	E2X26200					SHEET 1 OF 3		
INSPECTOR	B. Marquis	CONTRACTOR	NH boring Inc		DRILLER	B. Thompson		ELEVATION	28.0	
METHOD OF DRILLING		GROUNDWATER READINGS			DRILL RIG	CME-50T		DATUM	FT MSL	
82.0	Wash Boring w/Casing	DATE/TIME	DEPTH(ft)	REMARKS	SPT HAMMER	140 lb Auto		GRID	N	4941.715
90.0	NX Rock Core	7/2/2007	14	Upon Completion (In Casing)			COORD	E	5187.3648	
							DATE START	6/28/07		
							DATE END	7/2/07		

DEPTH (ft)	STRATA SYMBOL	SAMPLE DATA	SAMPLE NO.	DEPTH (ft)	REC. (in)/(%)	ELEV.	FIELD CLASSIFICATION AND REMARKS
		20 15 10 11	S-1	1 - 3	8		Removed Sidewalk brick and mortar Brown well graded SAND, fine to coarse, medium dense, trace asphalt (FILL).
5		9 9 8 5	S-2	4 - 6	6		Brown well graded SAND, fine to coarse, medium dense, trace gravel
10		12 16 16 16	S-3	9 - 11	12		Brown well graded SAND, fine to coarse, medium dense
15		32 29 31	S-4	14 - 15.5	0	▼	No Recovery
20		8 10 14	S-5	19 - 20.5	5	10.5	Brown Silty fine SAND
25		7 8 14	S-6	24 - 25.5	8		SAME
30		7 7 10	S-7	29 - 30.5	3		SAME
35		12	S-8	34 - 35.5	10		SAME

Page 1: 0-35 feet. Each subsequent page displays 40 feet.

COHESIVE SOIL		NON-COHESIVE SOIL		RELATIVE PROPORTIONS OF SOIL COMPONENTS		LEGEND					
BLOWS/FT	CONSISTENCY	BLOWS/FT	DENSITY			 Auger Sample (AS)	 Rock Core (RC) and RQD (%)	 Split-Spoon Sample (SS) and Blow Counts per 6" REC (in)	 Undisturbed (U)-Shelby Tube, (P)-Piston	 Jar Sample (JS)	 Bag Sample (B)
0 - 2 3 - 4 5 - 8 9 - 15 16 - 30 30 +	VERY SOFT SOFT MEDIUM STIFF STIFF VERY STIFF HARD	0 - 4 5 - 10 11 - 30 31 - 50 51 +	VERY LOOSE LOOSE MEDIUM DENSE DENSE VERY DENSE	< 10% 15 - 25% 30 - 45% 50 - 100%	TRACE LITTLE SOME MOSTLY	REFER TO THE SHEET ENTITLED "KEY TO DESCRIPTION AND CLASSIFICATION OF SUBSURFACE MATERIALS" FOR ADDITIONAL SYMBOLOGY.					
						BORING NO.		JE-B3			

LOG OF TEST BORING



PROJECT	DUDLEY SQUARE DEMOLITION PROJECT
LOCATION	2262 Washington Street
OWNER	BOSTON REDEVELOPMENT AUTHORITY
JOB NUMBER	E2X26200

BORING
NO.

JE-B3

SHEET 2 OF 3

DEPTH (ft)	STRATA SYMBOL	SAMPLE DATA	SAMPLE NO.	DEPTH (ft)	REC. (in)/(%)	ELEV.	FIELD CLASSIFICATION AND REMARKS
40		15 27					
40		18 18 28	S-9	39 - 40.5	11		Brown fine SAND , dense
45		11 16 24	S-10	44 - 45.5	18		Brown fine SAND, trace silt
50		23 29 35	S-11	49 - 50.5	13		Brown silty fine SAND with rusty thin layer of very fine sand, trace clumps of clay
55		16 16 36	S-12	54 - 55.5	18	-24.5	CLAY
60		28 34 43	S-13	59 - 60.5	13		SAME
65		14 14 17	S-14	64 - 65.5	16		CLAY with a thin lense of sand (Top 8"= clay, middle 4"=sand, bottom 4"=clay).
			U-1	66 - 68			(Wash boring to 66 ft. Shut down for the day) (Shelby tube)
70		40 40 50/0"	S-15	68 - 69	14	-40.0	Clayey TILL (gravel, sand and rock fragment)
			S-16	74 - 74.5	1		SAME (Refusal)

Page 1: 0-35 feet. Each subsequent page displays 40 feet.

COHESIVE SOIL		NON-COHESIVE SOIL		RELATIVE PROPORTIONS OF SOIL COMPONENTS		LEGEND	
BLOWS/FT	CONSISTENCY	BLOWS/FT	DENSITY				
0 - 2	VERY SOFT	0 - 4	VERY LOOSE	< 10%	TRACE	Auger Sample (AS)	Rock Core (RC) and RQD (%)
3 - 4	SOFT	5 - 10	LOOSE	15 - 25%	LITTLE	Split-Spoon Sample (SS) and Blow Counts per 6" REC (in)	Undisturbed (U)-Shelby Tube, (P)-Piston
5 - 8	MEDIUM STIFF	11 - 30	MEDIUM DENSE	30 - 45%	SOME	Jar Sample (JS)	Bag Sample (B)
9 - 15	STIFF	31 - 50	DENSE	50 - 100%	MOSTLY	REFER TO THE SHEET ENTITLED "KEY TO DESCRIPTION AND CLASSIFICATION OF SUBSURFACE MATERIALS" FOR ADDITIONAL SYMBOLOGY.	
16 - 30	VERY STIFF	51 +	VERY DENSE			BORING NO.	JE-B3
30 +	HARD						

LOG OF TEST BORING



PROJECT	DUDLEY SQUARE DEMOLITION PROJECT
LOCATION	2262 Washington Street
OWNER	BOSTON REDEVELOPMENT AUTHORITY
JOB NUMBER	E2X26200

**BORING
NO.**

JE-B3

SHEET 3 OF 3

DEPTH (ft)	STRATA SYMBOL	SAMPLE DATA	SAMPLE NO.	DEPTH (ft)	REC. (in)/(%)	ELEV.	FIELD CLASSIFICATION AND REMARKS
75		RQD=0	RC-1	82 - 87	20	-54.0	Wash boring to 82 ft.
80							(Probable to of Bedrock)
85			120/6"	89 - 89.5	6	-62.0	Rock fragments and gravel, severely weathered CONGLOMERATE rock. (Hole caved in at recovery of the barrel. Pull rod and capped pavement for the day.)
90							(Resume work on Monday 7/2/07. Difficulty dropping core barrel or driving casing beyond 87ft. Attempted to drive casing without luck. Telescope with 3" casing to 89ft. 3" core barrel could not be advanced. Took spilt spoon sample instead)
							Gray decomposed rock, soft.
							Bottom of Hole at 89.5'.
95							
100							
105							
110							

Page 1: 0-35 feet. Each subsequent page displays 40 feet.

COHESIVE SOIL		NON-COHESIVE SOIL		RELATIVE PROPORTIONS OF SOIL COMPONENTS		LEGEND					
BLOWS/FT	CONSISTENCY	BLOWS/FT	DENSITY			Auger Sample (AS)	Rock Core (RC) and RQD (%) REC (%)	Split-Spoon Sample (SS) and Blow Counts per 6" REC (in)	Undisturbed (U)-Shelby Tube, (P)-Piston	Jar Sample (JS)	Bag Sample (B)
0 - 2	VERY SOFT	0 - 4	VERY LOOSE	< 10%	TRACE						
3 - 4	SOFT	5 - 10	LOOSE	15 - 25%	LITTLE						
5 - 8	MEDIUM STIFF	11 - 30	MEDIUM DENSE	30 - 45%	SOME						
9 - 15	STIFF	31 - 50	DENSE	50 - 100%	MOSTLY						
16 - 30	VERY STIFF		VERY DENSE								
30 +	HARD	51 +									

REFER TO THE SHEET ENTITLED "KEY TO DESCRIPTION AND CLASSIFICATION OF SUBSURFACE MATERIALS" FOR ADDITIONAL SYMBOLOGY.

**BORING
NO.**

JE-B3

LOG OF TEST BORING

		PROJECT		DUDLEY SQUARE DEMOLITION PROJECT		BORING NO.		JE-B4											
		LOCATION		2262 Washington Street															
		OWNER		BOSTON REDEVELOPMENT AUTHORITY				SHEET 1 OF 3											
		JOB NUMBER		E2X26200															
INSPECTOR		B. Marquis		CONTRACTOR		NH Boring Inc		DRILLER		B. Thompson		ELEVATION		29.8					
METHOD OF DRILLING		GROUNDWATER READINGS		DRILL RIG		CME-50T		DATUM		FT MSL									
80.2		Wash Boring w/Casing		DATE/TIME		DEPTH(ft)		REMARKS		SPT HAMMER		140 lb Auto		GRID		N		4894.7989	
101.0		NX Rock Core		7/9/2007		17		24 hour reading		COORD		E		5182.0003					
										DATE START		7/3/07							
										DATE END		7/9/00							
DEPTH (ft)	STRATA SYMBOL	SAMPLE DATA	SAMPLE NO.	DEPTH (ft)	REC. (in)/(%)	ELEV.	FIELD CLASSIFICATION AND REMARKS												
		28 6 6	S-1	0 - 1.5	16		Brown and black SAND with miscellaneous construction debris. (FILL) (Sidewalk base material - brick and asphalt)												
5							(Probable boulder and granite blocks. Difficulty driving casing. Changed out casing when the sampling spoon could not be driven through pinched casing. Unable to take sample . Roller bit to 9.0ft)												
10		46 50/1"	S-2	9 - 9.6	5		Brown GRAVEL with sand. Trace crushed granite fragments, probable granite boulder (FILL)												
15		6 7 5	S-3	15 - 16.5	10		Brown well graded SAND, trace gravel. (Lost drilling fluid) (Difficulty driving casing below 16-ft)												
20		5 7 8	S-4	20 - 21.5	13		SAME (Due to damage and difficulty driving casing, extract 4-in ch casing and replaced with 5-inch casing and driven to 25-ft)												
25		6 7 8	S-5	25 - 26.5	12	6.8	Brown SILTY SAND, trace gravel												
30		6 7 7	S-6	30 - 31.5	16		SAME												
35																			

Page 1: 0-35 feet. Each subsequent page displays 40 feet.

COHESIVE SOIL		NON-COHESIVE SOIL		RELATIVE PROPORTIONS OF SOIL COMPONENTS		LEGEND					
BLOWS/FT	CONSISTENCY	BLOWS/FT	DENSITY			Auger Sample (AS)	Rock Core (RC) and RQD (%)	Split-Spoon Sample (SS) and Blow Counts per 6" REC (in)	Undisturbed (U)-Shelby Tube, (P)-Piston	Jar Sample (JS)	Bag Sample (B)
0 - 2 3 - 4 5 - 8 9 - 15 16 - 30 30 +	VERY SOFT SOFT MEDIUM STIFF STIFF VERY STIFF HARD	0 - 4 5 - 10 11 - 30 31 - 50 51 +	VERY LOOSE LOOSE MEDIUM DENSE DENSE VERY DENSE	< 10% 15 - 25% 30 - 45% 50 - 100%	TRACE LITTLE SOME MOSTLY	REFER TO THE SHEET ENTITLED "KEY TO DESCRIPTION AND CLASSIFICATION OF SUBSURFACE MATERIALS" FOR ADDITIONAL SYMBOLOGY.					
						BORING NO.		JE-B4			

JE JACOBS

DEPTH (ft)	STRATA SYMBOL	SAMPLE DATA	SAMPLE NO.	DEPTH (ft)	REC. (in)/(%)	ELEV.	FIELD CLASSIFICATION AND REMARKS
		 3 4 8	S-7	35 - 36.5	8		SAME
40		 4 6 12	S-8	40 - 41.5	18		Olive green SILTY SAND with 5-inch clay lense at top of spoon.
45		 6 8 12	S-9	45 - 46.5	14		Brown SILTY SAND
50		 4 10 16	S-10	50 - 51.5	16		Brown SILTY SAND with clumps of clay
55		 9 12 18	S-11	55 - 56.5	18		SAME
						-27.7	
60	 6 2 3	S-12	60 - 61.5	18			CLAYEY SAND TTop 9 inches) Bottom 9-inches = clay
			U-1	62 - 64	24		CLAY
65	 WOR 4 4	S-13	64 - 65.5	18			CLAY (Top 15-inch = clay, Bottom 3-inch = clayey sand and gravel)
						-36.2	
70	 25 20 22	S-14	70 - 71.5	17			Brown to black GRAVEL with silty coarse sand (TILL)

COHESIVE SOIL		NON-COHESIVE SOIL		RELATIVE PROPORTIONS OF SOIL COMPONENTS		LEGEND			
BLOWS/FT	CONSISTENCY	BLOWS/FT	DENSITY			 Auger Sample (AS)  Rock Core (RC) and RQD (%) REC (%)  Split-Spoon Sample (SS) and Blow Counts per 6" REC (in)  Undisturbed (U)-Shelby Tube, (P)-Piston  Jar Sample (JS)  Bag Sample (B)			
0 - 2	VERY SOFT	0 - 4	VERY LOOSE	< 10%	TRACE	REFER TO THE SHEET ENTITLED "KEY TO DESCRIPTION AND CLASSIFICATION OF SUBSURFACE MATERIALS" FOR ADDITIONAL SYMBOLOGY.		BORING NO.	JE-B4
3 - 4	SOFT	5 - 10	LOOSE	15 - 25%	LITTLE				
5 - 8	MEDIUM STIFF	11 - 30	MEDIUM DENSE	30 - 45%	SOME				
9 - 15	STIFF	31 - 50	DENSE	50 - 100%	MOSTLY				
16 - 30	VERY STIFF	51 +	VERY DENSE						
30 +	HARD								

LOG OF TEST BORING



PROJECT	DUDLEY SQUARE DEMOLITION PROJECT
LOCATION	2262 Washington Street
OWNER	BOSTON REDEVELOPMENT AUTHORITY
JOB NUMBER	E2X26200

BORING
NO.

JE-B4

SHEET 3 OF 3

DEPTH (ft)	STRATA SYMBOL	SAMPLE DATA	SAMPLE NO.	DEPTH (ft)	REC. (in)/(%)	ELEV.	FIELD CLASSIFICATION AND REMARKS
75		24 40 34	S-15	75 - 76.5	10		SAME with rust iron stain
80		65 61 100/2" RQD=0	S-16 RC-1	79 - 80.2 80.2 - 85	9 20	-50.2	Rust to brown TILL, very dense, intact. (Refusal may be possible top of Bedrock) <u>CONGLOMERATE</u> - Rust to brown, coarse grained with pebbles. Mostly gravel recovery or dissintegrated weak sedimentary rock. (Take split spoon sample)
85		27 66 71	S-17	85 - 86.5	14		Intact possible sedimentary bedrock <u>CONGLOMERATE</u> with pebblescoarse sand and silt
90		38 100/5" RQD=0	S-18 RC-2	89 - 89.9 91 - 96	9 20		Gray to brown <u>CONGLOMERATE</u> (Possible decomposed bedrock) <u>CONGLOMERATE</u> - brown, soft and fragile, disintegrates when squeezed by hand
95		RQD=33	RC-3	96 - 101	54		SAME
100						-71.2	Bottom of Hole at 101'.
105							
110							

Page 1: 0-35 feet. Each subsequent page displays 40 feet.

COHESIVE SOIL		NON-COHESIVE SOIL		RELATIVE PROPORTIONS OF SOIL COMPONENTS		LEGEND					
BLOWS/FT	CONSISTENCY	BLOWS/FT	DENSITY			Auger Sample (AS)	Rock Core (RC) and RQD (%)	Split-Spoon Sample (SS) and Blow Counts	Undisturbed (U)-Shelby Tube, (P)-Piston	Jar Sample (JS)	Bag Sample (B)
0 - 2	VERY SOFT	0 - 4	VERY LOOSE	< 10%	TRACE						
3 - 4	SOFT	5 - 10	LOOSE	15 - 25%	LITTLE						
5 - 8	MEDIUM STIFF	11 - 30	MEDIUM DENSE	30 - 45%	SOME						
9 - 15	STIFF	31 - 50	DENSE	50 - 100%	MOSTLY						
16 - 30	VERY STIFF	51 +	VERY DENSE								
30 +	HARD										

REFER TO THE SHEET ENTITLED "KEY TO DESCRIPTION AND CLASSIFICATION OF SUBSURFACE MATERIALS" FOR ADDITIONAL SYMBOLOGY.

BORING
NO.

JE-B4

LOG OF TEST PIT

		PROJECT		DUDLEY SQUARE		TEST PIT NO.		JE-TP1									
		LOCATION		2262 Washington Street													
		OWNER		BOSTON REDEVELOPMENT AUTHORITY													
		CONTRACTOR		NH Boring Inc		GROUNDWATER READING		OPERATOR		D Thompson							
EXCAVATOR		Mini Excavator		DATE/TIME		DEPTH(ft)		REMARKS									
BUCKET		0.25 cy															
						DATE START		7/12/2007									
						DATE END		7/12/2007									
DEPTH (ft)		STRATA SYMBOL		ELEV (ft)		FIELD CLASSIFICATION AND REMARKS		PLAN VIEW									
5				17.10		FILL, consisting of well graded sand, gravel boulders and construction debris.											
10																	
15																	
20																	
TEST PIT DIMENSION 8' X 6' X 3.5' Bottom portion of wall is comprised of Red mason bricks which is adjoined to the north with concrete slab																	
SKETCHES																	
REMARKS:																	
LEGEND WATER LEVEL JAR SAMPLE BAG SAMPLE																	
RELATIVE PROPORTIONS <table border="1"> <tr> <td>< 10%</td> <td>TRACE</td> </tr> <tr> <td>15 - 25%</td> <td>LITTLE</td> </tr> <tr> <td>30 - 45%</td> <td>SOME</td> </tr> <tr> <td>50 - 100%</td> <td>MOSTLY</td> </tr> </table>										< 10%	TRACE	15 - 25%	LITTLE	30 - 45%	SOME	50 - 100%	MOSTLY
< 10%	TRACE																
15 - 25%	LITTLE																
30 - 45%	SOME																
50 - 100%	MOSTLY																
TEST PIT NO. JE-TP1																	

LOG OF TEST PIT

			PROJECT		DUDLEY SQUARE		TEST PIT NO.		JE-TP-2																												
			LOCATION		2262 Washington Street																																
			OWNER		BOSTON REDEVELOPMENT AUTHORITY																																
			JOB NUMBER		E2X26200																																
CONTRACTOR		NH Boring Inc		GROUNDWATER READING		OPERATOR		D Thompson		ELEVATION		19.3																									
EXCAVATOR		Mini Excavator		DATE/TIME		DEPTH(ft)		REMARKS		INSPECTOR		B. Marquis		DATUM		FT MSL																					
BUCKET		0.25 cy								DATE START		7/12/2007		GRID		N 4881.0855																					
DEPTH (ft)		ST RATA SYMBOL		ELEV (ft)		FIELD CLASSIFICATION AND REMARKS		DATE END		7/12/2007		COORD		E 5123.5457		PLAN VIEW																					
5				12.80		FILL, well graded sand and miscellaneous construction debris																															
10						Excavated TP to expose bottom of footing. Undermine bottom of footing with Shovel																															
15																																					
20																																					
SKETCHES																																					
SECTION A-A PLAN VIEW NTS																																					
REMARKS: LEGEND WATER LEVEL JAR SAMPLE BAG SAMPLE <table border="1"> <thead> <tr> <th colspan="2">RELATIVE PROPORTIONS</th> <th rowspan="2">TEST PIT NO.</th> <th rowspan="2">JE-TP-2</th> </tr> </thead> <tbody> <tr> <td>< 10%</td> <td>TRACE</td> <td></td> <td></td> </tr> <tr> <td>15 - 25%</td> <td>LITTLE</td> <td></td> <td></td> </tr> <tr> <td>30 - 45%</td> <td>SOME</td> <td></td> <td></td> </tr> <tr> <td>50 - 100%</td> <td>MOSTLY</td> <td></td> <td></td> </tr> </tbody> </table>																		RELATIVE PROPORTIONS		TEST PIT NO.	JE-TP-2	< 10%	TRACE			15 - 25%	LITTLE			30 - 45%	SOME			50 - 100%	MOSTLY		
RELATIVE PROPORTIONS		TEST PIT NO.	JE-TP-2																																		
< 10%	TRACE																																				
15 - 25%	LITTLE																																				
30 - 45%	SOME																																				
50 - 100%	MOSTLY																																				

LOG OF TEST PIT

			PROJECT		DUDLEY SQUARE		TEST PIT NO.		JE-TP-3								
			LOCATION		2262 Washington Street												
			OWNER		BOSTON REDEVELOPMENT AUTHORITY		SHEET 1 OF 1										
			JOB NUMBER		E2X26200												
CONTRACTOR		NH Boring Inc		GROUNDWATER READING		OPERATOR		D Thompson		ELEVATION		20					
EXCAVATOR		Mini Excavator		DATE/TIME		DEPTH(ft)		REMARKS		INSPECTOR		B. Marquis		DATUM		FT MSL	
BUCKET		0.25 cy								DATE START		7/12/2007		GRID		N NOT	
										DATE END		7/12/2007		COORD		E SURVEYED	
DEPTH (ft)	STRATA SYMBOL	ELEV (ft)	FIELD CLASSIFICATION AND REMARKS						PLAN VIEW								
5		15.50	FILL, consisting of well graded sand, gravel boulders and construction debris. Test Pit is Located in the basement Level. Excavated TP to expose bottom of footing. Undermine bottom of footing with shovel Test Pit Dimension 103" X 60" X 58"														
10																	
15																	
20																	
SKETCHES																	
<u>A-A</u> NTS PLAN NTS																	
REMARKS:						WATER LEVEL JAR SAMPLE BAG SAMPLE											
						RELATIVE PROPORTIONS < 10% 15 - 25% 30 - 45% 50 - 100% TRACE LITTLE SOME MOSTLY								TEST PIT NO.		JE-TP-3	

LOG OF TEST PIT

			PROJECT		DUDLEY SQUARE		TEST PIT NO.		JE-TP-4																																				
			LOCATION		2262 Washington Street																																								
			OWNER		BOSTON REDEVELOPMENT AUTHORITY																																								
			JOB NUMBER		E2X26200																																								
CONTRACTOR		NH Boring Inc		GROUNDWATER READING		OPERATOR		D Thompson		ELEVATION		20																																	
EXCAVATOR		Mini Excavator		DATE/TIME		DEPTH(ft)		REMARKS		INSPECTOR		B. Marquis		DATUM		FT MSL																													
BUCKET		0.25 cy								DATE START		7/12/2007		GRID		N NOT																													
										DATE END		7/12/2007		COORD		E SURVEYED																													
DEPTH (ft)	STRATA SYMBOL	ELEV (ft)	FIELD CLASSIFICATION AND REMARKS						PLAN VIEW																																				
5		16.50	FILL, well graded sand																																										
10			JE-TP4 is Located in the basement and installed on the opposite side of JE-TP2 TEST PIT DIMENSION 7' x 5' x 3.5'																																										
15																																													
20																																													
SKETCHES																																													
REMARKS:																																													
<table border="1"> <tr> <td colspan="4">LEGEND</td> </tr> <tr> <td></td> <td>WATER LEVEL</td> <td></td> <td>JAR SAMPLE</td> </tr> <tr> <td></td> <td>BAG SAMPLE</td> <td colspan="2"></td> </tr> <tr> <td colspan="4">RELATIVE PROPORTIONS</td> </tr> <tr> <td>< 10%</td> <td>TRACE</td> <td colspan="2" rowspan="3">TEST PIT NO.</td> </tr> <tr> <td>15 - 25%</td> <td>LITTLE</td> </tr> <tr> <td>30 - 45%</td> <td>SOME</td> </tr> <tr> <td>50 - 100%</td> <td>MOSTLY</td> <td colspan="2"></td> </tr> <tr> <td colspan="4">JE-TP-4</td> </tr> </table>														LEGEND					WATER LEVEL		JAR SAMPLE		BAG SAMPLE			RELATIVE PROPORTIONS				< 10%	TRACE	TEST PIT NO.		15 - 25%	LITTLE	30 - 45%	SOME	50 - 100%	MOSTLY			JE-TP-4			
LEGEND																																													
	WATER LEVEL		JAR SAMPLE																																										
	BAG SAMPLE																																												
RELATIVE PROPORTIONS																																													
< 10%	TRACE	TEST PIT NO.																																											
15 - 25%	LITTLE																																												
30 - 45%	SOME																																												
50 - 100%	MOSTLY																																												
JE-TP-4																																													

Attachment B

Lab Results

1145 Massachusetts Avenue
Boxborough, MA 01719
978 635 0424 Tel
978 635 0266 Fax

Geotechnical Test Report

August 21, 2007

GTX-7642 BRA/Dudley Square – E2X26200 Project

Prepared for:

Jacobs Civil, Inc.

Client:	Jacobs Civil, Inc.	Project No:	GTX-7642
Project:	BRA/Dudley Square-E2X26200	Tested By:	jbr
Location:		Checked By:	n/a
Boring ID: ---	Sample Type: ---	Test Date:	08/20/07
Sample ID:---	Test Date:	Sample Id:	---
Depth : ---			


Moisture Content of Soil - ASTM D 2216

Boring ID	Sample ID	Depth	Description	Moisture Content, %
JE-B3	JE-B3-ST1	66-68 ft	Moist, greenish gray clay	38
JE-B4	JE-B4-ST1	62-64 ft	Moist, greenish gray clay	35

Notes: Temperature of Drying : 110° Celsius

Client:	Jacobs Civil, Inc.	Project No:	GTX-7642
Project:	BRA/Dudley Square-E2X26200	Tested By:	jbr
Location:		Checked By:	njh
Boring ID:	JE-B1	Sample Type:	jar
Sample ID:	S-7	Test Date:	08/07/07
Depth :	30-31.5 ft	Test Id:	116666
Test Comment:	---		
Sample Description:	Moist, medium olive brown sand with silt		
Sample Comment:	---		

Particle Size Analysis - ASTM D 422



% Cobble	% Gravel	% Sand	% Silt & Clay Size
--	--	93.4	6.6

Sieve Name	Sieve Size, mm	Percent Finer	Spec. Percent	Complies
#4	4.75	100		
#10	2.00	100		
#20	0.84	98		
#40	0.42	86		
#60	0.25	48		
#100	0.15	17		
#200	0.074	7		

Coefficients

D ₈₅ = 0.4201 mm	D ₃₀ = 0.1861 mm
D ₆₀ = 0.2946 mm	D ₁₅ = 0.1345 mm
D ₅₀ = 0.2556 mm	D ₁₀ = 0.0944 mm
C _u = 3.121	C _c = 1.245

Classification

ASTM N/A


AASHTO Fine Sand (A-3 (0))

Sample/Test Description

Sand/Gravel Particle Shape : **ROUNDED**
Sand/Gravel Hardness : **HARD**

Client:	Jacobs Civil, Inc.	Project No:	GTX-7642
Project:	BRA/Dudley Square-E2X26200	Tested By:	jbr
Location:		Checked By:	njh
Boring ID:	JE-B2	Sample Type:	jar
Sample ID:	S-14B	Test Date:	08/12/07
Depth :	62-64 ft	Test Id:	116667
Test Comment:	---		
Sample Description:	Moist, dark yellowish brown clayey sand with gravel		
Sample Comment:	---		

Particle Size Analysis - ASTM D 422



% Cobble	% Gravel	% Sand	% Silt & Clay Size
--	35.2	36.5	28.3

Sieve Name	Sieve Size, mm	Percent Finer	Spec. Percent	Complies
1 inch	25.00	100		
3/4 inch	19.00	86		
1/2 inch	12.70	78		
3/8 inch	9.51	71		
#4	4.75	65		
#10	2.00	58		
#20	0.84	52		
#40	0.42	45		
#60	0.25	40		
#100	0.15	36		
#200	0.074	28		

Coefficients

D ₈₅ = 18.0553 mm	D ₃₀ = 0.0868 mm
D ₆₀ = 2.6399 mm	D ₁₅ = N/A
D ₅₀ = 0.7152 mm	D ₁₀ = N/A
C _u = N/A	C _c = N/A

Classification


ASTM	N/A
AASHTO	Silty Gravel and Sand (A-2-4 (0))

Sample/Test Description

Sand/Gravel Particle Shape : ANGULAR
Sand/Gravel Hardness : HARD

Client: Jacobs Civil, Inc.	Project: BRA/Dudley Square-E2X26200	Project No: GTX-7642
Location:	Boring ID: JE-B3	Sample Type: tube
Tested By: jbr	Sample ID: JE-B3-ST1	Test Date: 08/14/07
Checked By: njh	Depth: 66-68 ft	Test Id: 116668
Test Comment: ---		
Sample Description: Moist, greenish gray clay		
Sample Comment: ---		

Particle Size Analysis - ASTM D 422



% Cobble	% Gravel	% Sand	% Silt & Clay Size
---	0.0	3.5	96.5

Sieve Name	Sieve Size, mm	Percent Finer	Spec. Percent	Complies
#4	4.75	100		
#10	2.00	100		
#20	0.84	100		
#40	0.42	100		
#60	0.25	99		
#100	0.15	98		
#200	0.074	96		
---	Particle Size (mm)	Percent Finer	Spec. Percent	Complies
---	0.0260	94		
---	0.0158	89		
---	0.0097	85		
---	0.0060	77		
---	0.0049	71		
---	0.0034	64		
---	0.0027	59		
---	0.0012	43		

Coefficients

D ₈₅ = 0.0100 mm	D ₃₀ = N/A
D ₆₀ = 0.0028 mm	D ₁₅ = N/A
D ₅₀ = 0.0017 mm	D ₁₀ = N/A
C _u = N/A	C _c = N/A

Classification

ASTM lean clay (CL)


AASHTO Clayey Soils (A-7-6 (28))

Sample/Test Description

Sand/Gravel Particle Shape : ROUNDED
Sand/Gravel Hardness : HARD

Client:	Jacobs Civil, Inc.	Project No:	GTX-7642
Project:	BRA/Dudley Square-E2X26200	Tested By:	jbr
Location:		Checked By:	jdt
Boring ID:	JE-B4	Sample Type:	tube
Sample ID:	JE-B4-ST1	Test Date:	08/15/07
Depth :	62-64 ft	Test Id:	116669
Test Comment:	Hydrometer portion only as requested.		
Sample Description:	Moist, greenish gray clay		
Sample Comment:	---		

Particle Size Analysis - ASTM D 422-63 (reapproved 2002)



% Cobble	% Gravel	% Sand	% Silt & Clay Size
---	---	---	---

Sieve Name	Sieve Size, mm	Percent Finer	Spec. Percent	Complies
---	Particle Size (mm)	Percent Finer	Spec. Percent	Complies
---	0.0276	99		
---	0.0176	97		
---	0.0105	90		
---	0.0075	86		
---	0.0054	81		
---	0.0039	75		
---	0.0028	69		
---	0.0017	62		

Coefficients

D ₈₅ = 0.0070 mm	D ₃₀ = N/A
D ₆₀ = N/A	D ₁₅ = N/A
D ₅₀ = N/A	D ₁₀ = N/A
C _u = N/A	C _c = N/A

Classification

ASTM N/A

AASHTO ()

Sample/Test Description

Sand/Gravel Particle Shape :

Sand/Gravel Hardness :



Project: BRA/Dudley Square-E2X26200

Location:

Project No: GTX-7642

Sample Type: jar

Tested By: jbr

Test Date: 08/09/07


Checked By: idt

Test Id: 116670

Sample Description: Moist, olive clay

Sample Comment: ---

Particle Size Analysis - ASTM D 422-63 (reapproved 2002)



% Cobble	% Gravel	% Sand	% Silt & Clay Size
—	—	—	—

Sieve Name	Sieve Size, mm	Percent Finer	Spec. Percent	Complies
---	Particle Size (mm)	Percent Finer	Spec. Percent	Complies
---	0.0340	14		
---	0.0220	11		
---	0.0128	9		
---	0.0091	8		
---	0.0065	5		
---	0.0046	4		
---	0.0033	3		
---	0.0013	2		

Coefficients

$$D_{30} = N/A$$
$$D_{15} = N/A$$
$$D_{10} = 0.0179 \text{ mm}$$
$$C_c = N/A$$

Classification

ASTM N/A

AASHTO ()


Sample/Test Description	Test Result	Test Date	Tested By	Reviewed By	Signature	Signature
1. Pre-Test						
2. Test						
3. Post-Test						
4. Test						
5. Post-Test						
6. Test						
7. Post-Test						
8. Test						
9. Post-Test						
10. Test						
11. Post-Test						
12. Test						
13. Post-Test						
14. Test						
15. Post-Test						
16. Test						
17. Post-Test						
18. Test						
19. Post-Test						
20. Test						
21. Post-Test						
22. Test						
23. Post-Test						
24. Test						
25. Post-Test						
26. Test						
27. Post-Test						
28. Test						
29. Post-Test						
30. Test						
31. Post-Test						
32. Test						
33. Post-Test						
34. Test						
35. Post-Test						
36. Test						
37. Post-Test						
38. Test						
39. Post-Test						
40. Test						
41. Post-Test						
42. Test						
43. Post-Test						
44. Test						
45. Post-Test						
46. Test						
47. Post-Test						
48. Test						
49. Post-Test						
50. Test						
51. Post-Test						
52. Test						
53. Post-Test						
54. Test						
55. Post-Test						
56. Test						
57. Post-Test						
58. Test						
59. Post-Test						
60. Test						
61. Post-Test						
62. Test						
63. Post-Test						
64. Test						
65. Post-Test						
66. Test						
67. Post-Test						
68. Test						
69. Post-Test						
70. Test						
71. Post-Test						
72. Test						
73. Post-Test						
74. Test						
75. Post-Test						
76. Test						

Sand/Gravel Particle Shape :

Sand/Gravel Hardness :

Client:	Jacobs Civil, Inc.	Project No:	GTX-7642
Project:	BRA/Dudley Square-E2X26200	Tested By:	ap
Location:		Checked By:	njh
Boring ID:	JE-B3	Sample Type:	tube
Sample ID:	JE-B3-ST1	Test Date:	08/15/07
Depth :	66-68 ft	Test Id:	116664
Test Comment:	---		
Sample Description:	Moist, greenish gray clay		
Sample Comment:	---		

Atterberg Limits - ASTM D 4318



Symbol	Sample ID	Boring	Depth	Natural Moisture Content, %	Liquid Limit	Plastic Limit	Plasticity Index	Liquidity Index	Soil Classification
*	JE-B3-ST1	JE-B3	66-68 ft	38	43	17	26	1	lean clay (CL)

Sample Prepared using the WET method

0% Retained on #40 Sieve


Dry Strength: VERY HIGH

Dilatancy: SLOW

Toughness: LOW

Client:	Jacobs Civil, Inc.	Project No:	GTX-7642
Project:	BRA/Dudley Square-E2X26200	Tested By:	ap
Location:		Checked By:	njh
Boring ID:	JE-B4	Sample Type:	tube
Sample ID:	JE-B4-ST1	Test Date:	08/06/07
Depth :	62-64 ft	Test Id:	116665
Test Comment:	---		
Sample Description:	Moist, greenish gray clay		
Sample Comment:	---		

Atterberg Limits - ASTM D 4318



Symbol	Sample ID	Boring	Depth	Natural Moisture Content, %	Liquid Limit	Plastic Limit	Plasticity Index	Liquidity Index	Soil Classification
*	JE-B4-ST1	JE-B4	62-64 ft	35	52	22	30	0	



Sample Prepared using the WET method

Dry Strength: VERY HIGH

Dilatancy: SLOW


Toughness: LOW

CONSOLIDATION TEST DATA SUMMARY REPORT



GeoTesting express a subsidiary of Geocomp Corporation	Project: BRA/Dudley Square	Location: ---	Project No.: GTX-7642
	Boring No.: JE-B-4	Tested By: md	Checked By: jdt
	Sample No.: JE B4 ST-1	Test Date: 08/02/07	Depth: 62-64 ft
	Test No.: C-1	Sample Type: Tube	Elevation: ---
	Description: Moist, greenish gray clay		
	Remarks: System C		

CONSOLIDATION TEST DATA SUMMARY REPORT



					Before Test	After Test
Overburden Pressure: ---				Water Content, %	46.41	34.54
Preconsolidation Pressure: ---				Dry Unit Weight, pcf	76.3	89.26
Compression Index: ---				Saturation, %	99.99	100.00
Diameter: 2.5 in		Height: 1 in		Void Ratio	1.31	0.98
LL: 52	PL: 22	PI: 30	GS: 2.82			

GeoTesting express a subsidiary of Geocomp Corporation	Project: BRA/Dudley Square	Location: ---	Project No.: GTX-7642
	Boring No.: JE-B-4	Tested By: md	Checked By: jdt
	Sample No.: JE B4 ST-1	Test Date: 08/02/07	Depth: 62-64 ft
	Test No.: C-1	Sample Type: Tube	Elevation: ---
	Description: Moist, greenish gray clay		
	Remarks: System C		

CONSOLIDATION TEST DATA

Project: BRA/Dudley Square
 Boring No.: JE-B-4
 Sample No.: JE B4 ST-1
 Test No.: C-1

Location: ---
 Tested By: md
 Test Date: 08/02/07
 Sample Type: Tube

Project No.: GTX-7642
 Checked By: jdt
 Depth: 62-64 ft
 Elevation: ---

Soil Description: Moist, greenish gray clay
 Remarks: System C

Estimated Specific Gravity: 2.82
 Initial Void Ratio: 1.31
 Final Void Ratio: 0.98

Liquid Limit: 52
 Plastic Limit: 22
 Plasticity Index: 30

Initial Height: 1.00 in
 Specimen Diameter: 2.50 in

	Before Consolidation		After Consolidation	
	Trimmings	Specimen+Ring	Specimen+Ring	Trimmings
Container ID	3	RING		2050
Wt. Container + Wet Soil, gm	131.7	254.94	243.27	141.61
Wt. Container + Dry Soil, gm	97.58	209.31	209.31	107.35
Wt. Container, gm	8.08	110.99	110.99	8.16
Wt. Dry Soil, gm	89.5	98.32	98.32	99.19
Water Content, %	38.12	46.41	34.54	34.54
Void Ratio	---	1.31	0.98	---
Degree of Saturation, %	---	99.99	100.00	---
Dry Unit Weight, pcf	---	76.305	89.258	---

Note: Specific Gravity and Void Ratios are calculated assuming the degree of saturation equals 100% at the end of the test. Therefore, values may not represent actual values for the specimen.

CONSOLIDATION TEST DATA

Project: BRA/Dudley Square
Boring No.: JE-B-4
Sample No.: JE B4 ST-1
Test No.: C-1

Location: ---
Tested By: md
Test Date: 08/02/07
Sample Type: Tube

Project No.: GTX-7642
Checked By: jdt
Depth: 62-64 ft
Elevation: ---

Soil Description: Moist, greenish gray clay
Remarks: System C



	Applied	Final	Void	Strain	T50 Fitting		Coefficient of Consolidation		
	Stress	Displacement			Sq.Rt.	Log	Sq.Rt.	Log	Ave.
	tsf	in	Ratio	at End	min	min	in ² /sec	in ² /sec	in ² /sec
1	0.125	-8.741e-005	1.311	-0.01	0.0	0.0	2.79e-002	0.00e+000	2.79e-002
2	0.25	0.001457	1.308	0.15	1.7	0.0	4.90e-004	0.00e+000	4.90e-004
3	0.5	0.005896	1.297	0.59	0.6	0.0	1.30e-003	0.00e+000	1.30e-003
4	1	0.01254	1.282	1.25	0.4	0.0	1.86e-003	0.00e+000	1.86e-003
5	2	0.02361	1.256	2.36	0.3	0.0	2.43e-003	0.00e+000	2.43e-003
6	4	0.03834	1.222	3.83	0.7	0.0	1.15e-003	0.00e+000	1.15e-003
7	8	0.06395	1.163	6.40	1.3	1.6	5.52e-004	4.70e-004	5.07e-004
8	4	0.06095	1.170	6.10	0.3	0.0	2.89e-003	0.00e+000	2.89e-003
9	2	0.05624	1.181	5.62	0.9	0.0	7.72e-004	0.00e+000	7.72e-004
10	1	0.05121	1.193	5.12	2.1	2.5	3.49e-004	2.92e-004	3.18e-004
11	2	0.05307	1.188	5.31	0.5	0.0	1.56e-003	0.00e+000	1.56e-003
12	4	0.05819	1.177	5.82	0.5	0.0	1.50e-003	0.00e+000	1.50e-003
13	8	0.0698	1.150	6.98	0.9	0.8	8.32e-004	9.56e-004	8.90e-004
14	16	0.1336	1.002	13.36	3.3	3.7	2.03e-004	1.81e-004	1.92e-004
15	32	0.2104	0.825	21.04	2.8	3.3	2.01e-004	1.71e-004	1.85e-004
16	8	0.1941	0.863	19.41	0.5	0.0	9.92e-004	0.00e+000	9.92e-004
17	2	0.1707	0.916	17.07	4.7	5.7	1.16e-004	9.64e-005	1.05e-004
18	0.5	0.1451	0.976	14.51	18.5	16.9	3.15e-005	3.45e-005	3.29e-005

CONSOLIDATION TEST DATA

TIME CURVES

Constant Load Step: 1 of 18

Stress: 0.125 tsf





GeoTesting express a subsidiary of Geocomp Corporation	Project: BRA/Dudley Square	Location: ---	Project No.: GTX-7642
	Boring No.: JE-B-4	Tested By: md	Checked By: jdt
	Sample No.: JE B4 ST-1	Test Date: 08/02/07	Depth: 62-64 ft
	Test No.: C-1	Sample Type: Tube	Elevation: ---
	Description: Moist, greenish gray clay		
	Remarks: System C		

CONSOLIDATION TEST DATA

TIME CURVES

Constant Load Step: 2 of 18

Stress: 0.25 tsf





GeoTesting express a subsidiary of Geocomp Corporation	Project: BRA/Dudley Square	Location: ---	Project No.: GTX-7642
	Boring No.: JE-B-4	Tested By: md	Checked By: jdt
	Sample No.: JE B4 ST-1	Test Date: 08/02/07	Depth: 62-64 ft
	Test No.: C-1	Sample Type: Tube	Elevation: ---
	Description: Moist, greenish gray clay		
	Remarks: System C		

CONSOLIDATION TEST DATA

TIME CURVES

Constant Load Step: 3 of 18

Stress: 0.5 tsf





GeoTesting express a subsidiary of Geocomp Corporation	Project: BRA/Dudley Square	Location: ---	Project No.: GTX-7642
	Boring No.: JE-B-4	Tested By: md	Checked By: jdt
	Sample No.: JE B4 ST-1	Test Date: 08/02/07	Depth: 62-64 ft
	Test No.: C-1	Sample Type: Tube	Elevation: ---
	Description: Moist, greenish gray clay		
	Remarks: System C		

CONSOLIDATION TEST DATA

TIME CURVES

Constant Load Step: 4 of 18

Stress: 1. tsf





GeoTesting express a subsidiary of Geocomp Corporation	Project: BRA/Dudley Square	Location: ---	Project No.: GTX-7642
	Boring No.: JE-B-4	Tested By: md	Checked By: jdt
	Sample No.: JE B4 ST-1	Test Date: 08/02/07	Depth: 62-64 ft
	Test No.: C-1	Sample Type: Tube	Elevation: ---
	Description: Moist, greenish gray clay		
	Remarks: System C		

CONSOLIDATION TEST DATA

TIME CURVES

Constant Load Step: 5 of 18

Stress: 2. tsf





GeoTesting express a subsidiary of Geocomp Corporation	Project: BRA/Dudley Square	Location: ---	Project No.: GTX-7642
	Boring No.: JE-B-4	Tested By: md	Checked By: jdt
	Sample No.: JE B4 ST-1	Test Date: 08/02/07	Depth: 62-64 ft
	Test No.: C-1	Sample Type: Tube	Elevation: ---
	Description: Moist, greenish gray clay		
	Remarks: System C		

CONSOLIDATION TEST DATA

TIME CURVES

Constant Load Step: 6 of 18

Stress: 4. tsf





GeoTesting express a subsidiary of Geocomp Corporation	Project: BRA/Dudley Square	Location: ---	Project No.: GTX-7642
	Boring No.: JE-B-4	Tested By: md	Checked By: jdt
	Sample No.: JE B4 ST-1	Test Date: 08/02/07	Depth: 62-64 ft
	Test No.: C-1	Sample Type: Tube	Elevation: ---
	Description: Moist, greenish gray clay		
	Remarks: System C		

CONSOLIDATION TEST DATA

TIME CURVES

Constant Load Step: 7 of 18

Stress: 8. tsf





GeoTesting express a subsidiary of Geocomp Corporation	Project: BRA/Dudley Square	Location: ---	Project No.: GTX-7642
	Boring No.: JE-B-4	Tested By: md	Checked By: jdt
	Sample No.: JE B4 ST-1	Test Date: 08/02/07	Depth: 62-64 ft
	Test No.: C-1	Sample Type: Tube	Elevation: ---
	Description: Moist, greenish gray clay		
	Remarks: System C		

CONSOLIDATION TEST DATA

TIME CURVES

Constant Load Step: 8 of 18

Stress: 4. tsf





GeoTesting express a subsidiary of Geocomp Corporation	Project: BRA/Dudley Square	Location: ---	Project No.: GTX-7642
	Boring No.: JE-B-4	Tested By: md	Checked By: jdt
	Sample No.: JE B4 ST-1	Test Date: 08/02/07	Depth: 62-64 ft
	Test No.: C-1	Sample Type: Tube	Elevation: ---
	Description: Moist, greenish gray clay		
	Remarks: System C		

CONSOLIDATION TEST DATA

TIME CURVES

Constant Load Step: 9 of 18

Stress: 2. tsf





GeoTesting express a subsidiary of Geocomp Corporation	Project: BRA/Dudley Square	Location: ---	Project No.: GTX-7642
	Boring No.: JE-B-4	Tested By: md	Checked By: jdt
	Sample No.: JE B4 ST-1	Test Date: 08/02/07	Depth: 62-64 ft
	Test No.: C-1	Sample Type: Tube	Elevation: ---
	Description: Moist, greenish gray clay		
	Remarks: System C		

CONSOLIDATION TEST DATA

TIME CURVES

Constant Load Step: 10 of 18

Stress: 1. tsf





GeoTesting express a subsidiary of Geocomp Corporation	Project: BRA/Dudley Square	Location: ---	Project No.: GTX-7642
	Boring No.: JE-B-4	Tested By: md	Checked By: jdt
	Sample No.: JE B4 ST-1	Test Date: 08/02/07	Depth: 62-64 ft
	Test No.: C-1	Sample Type: Tube	Elevation: ---
	Description: Moist, greenish gray clay		
	Remarks: System C		

CONSOLIDATION TEST DATA

TIME CURVES

Constant Load Step: 11 of 18

Stress: 2. tsf





GeoTesting express a subsidiary of Geocomp Corporation	Project: BRA/Dudley Square	Location: ---	Project No.: GTX-7642
	Boring No.: JE-B-4	Tested By: md	Checked By: jdt
	Sample No.: JE B4 ST-1	Test Date: 08/02/07	Depth: 62-64 ft
	Test No.: C-1	Sample Type: Tube	Elevation: ---
	Description: Moist, greenish gray clay		
	Remarks: System C		

CONSOLIDATION TEST DATA

TIME CURVES

Constant Load Step: 12 of 18

Stress: 4. tsf





GeoTesting express a subsidiary of Geocomp Corporation	Project: BRA/Dudley Square	Location: ---	Project No.: GTX-7642
	Boring No.: JE-B-4	Tested By: md	Checked By: jdt
	Sample No.: JE B4 ST-1	Test Date: 08/02/07	Depth: 62-64 ft
	Test No.: C-1	Sample Type: Tube	Elevation: ---
	Description: Moist, greenish gray clay		
	Remarks: System C		

CONSOLIDATION TEST DATA

TIME CURVES

Constant Load Step: 13 of 18

Stress: 8. tsf





GeoTesting express a subsidiary of Geocomp Corporation	Project: BRA/Dudley Square	Location: ---	Project No.: GTX-7642
	Boring No.: JE-B-4	Tested By: md	Checked By: jdt
	Sample No.: JE B4 ST-1	Test Date: 08/02/07	Depth: 62-64 ft
	Test No.: C-1	Sample Type: Tube	Elevation: ---
	Description: Moist, greenish gray clay		
	Remarks: System C		

CONSOLIDATION TEST DATA

TIME CURVES

Constant Load Step: 14 of 18

Stress: 16. tsf





GeoTesting express a subsidiary of Geocomp Corporation	Project: BRA/Dudley Square	Location: ---	Project No.: GTX-7642
	Boring No.: JE-B-4	Tested By: md	Checked By: jdt
	Sample No.: JE B4 ST-1	Test Date: 08/02/07	Depth: 62-64 ft
	Test No.: C-1	Sample Type: Tube	Elevation: ---
	Description: Moist, greenish gray clay		
	Remarks: System C		

CONSOLIDATION TEST DATA

TIME CURVES

Constant Load Step: 15 of 18

Stress: 32. tsf





GeoTesting express a subsidiary of Geocomp Corporation	Project: BRA/Dudley Square	Location: ---	Project No.: GTX-7642
	Boring No.: JE-B-4	Tested By: md	Checked By: jdt
	Sample No.: JE B4 ST-1	Test Date: 08/02/07	Depth: 62-64 ft
	Test No.: C-1	Sample Type: Tube	Elevation: ---
	Description: Moist, greenish gray clay		
	Remarks: System C		

CONSOLIDATION TEST DATA

TIME CURVES

Constant Load Step: 16 of 18

Stress: 8. tsf





GeoTesting express a subsidiary of Geocomp Corporation	Project: BRA/Dudley Square	Location: ---	Project No.: GTX-7642
	Boring No.: JE-B-4	Tested By: md	Checked By: jdt
	Sample No.: JE B4 ST-1	Test Date: 08/02/07	Depth: 62-64 ft
	Test No.: C-1	Sample Type: Tube	Elevation: ---
	Description: Moist, greenish gray clay		
	Remarks: System C		

CONSOLIDATION TEST DATA

TIME CURVES

Constant Load Step: 17 of 18

Stress: 2. tsf





GeoTesting express a subsidiary of Geocomp Corporation	Project: BRA/Dudley Square	Location: ---	Project No.: GTX-7642
	Boring No.: JE-B-4	Tested By: md	Checked By: jdt
	Sample No.: JE B4 ST-1	Test Date: 08/02/07	Depth: 62-64 ft
	Test No.: C-1	Sample Type: Tube	Elevation: ---
	Description: Moist, greenish gray clay		
	Remarks: System C		

CONSOLIDATION TEST DATA


TIME CURVES

Constant Load Step: 18 of 18

Stress: 0.5 tsf



GeoTesting express a subsidiary of Geocomp Corporation	Project: BRA/Dudley Square	Location: ---	Project No.: GTX-7642
	Boring No.: JE-B-4	Tested By: md	Checked By: jdt
	Sample No.: JE B4 ST-1	Test Date: 08/02/07	Depth: 62-64 ft
	Test No.: C-1	Sample Type: Tube	Elevation: ---
	Description: Moist, greenish gray clay		
	Remarks: System C		



Client:	Jacobs Civil, Inc.
Project Name:	BRA/Dudley Square - E2X26200
Project Location:	---
GTX #:	7642
Test Date:	08/10/07
Tested By:	md
Checked By:	jdt

Bulk Density and Compressive Strength of Rock Core Specimens by ASTM D 2938

Boring ID	Sample ID	Depth, in	Bulk Density, lb/ft ³	Compressive Strength, psi	In conformance with ASTM D 4543
JE-B1	RC-1	64-69 ft	162	2,705	NO

Notes: Density determined on rock core samples by measuring dimensions and weight and then calculating.

All specimens tested at the approximate as-received moisture content and at standard laboratory temperature.

See attached photographs for specimen break type


Sample did not meet requirements of ASTM D 4353 because of pitted and uneven sides.

Client:	Jacobs Civil, Inc.	Test Date:	08/07/07
Project Name:	BRA/Dudley Square - E2X26200	Tested By:	md
Project Location:	---	Checked By:	jdt
GTX #:	7642		
Boring ID:	JE-B1		
Sample ID:	RC-1		
Depth:	64-69 ft		

UNIT WEIGHT DETERMINATION AND DIMENSIONAL AND SHAPE TOLERANCES OF ROCK CORE SPECIMENS BY ASTM D 4543

SAMPLE PREPARATION		---			
MOISTURE CONTENT		BULK DENSITY			
Tare ID:	---	1	2	3	Average
Wet Mass & Tare, g:	---	3.97	3.97	3.97	3.970
Dry Mass & Tare, g:	---	1.98	1.98	1.96	1.973
Mass Tare, g:	---	---	---	516	516
Moisture Content, %	---	162	---	---	---
		Specimen Length, in:		Specimen Diameter, in:	
		Specimen Mass, g:		Bulk Density, lb/ft ³	
		Dry Density, lb/ft ³			
DEVIATION FROM STRAIGHTNESS		Max	Min	Difference	
Measurements at 0°, in		0.00780	-0.01895	0.02675	
Measurements at 120°, in		0.02670	-0.00505	0.03175	
Measurements at 240°, in		0.00180	-0.01555	0.01735	
		Maximum difference must be < 0.020 in.			
		Straightness Tolerance Met?			
		NO			
FLATNESS		-1/2"	-3/8"	-1/4"	-1/8"
END 1					
Measurements at 0°, in		---	---	---	---
Measurements at 120°, in		---	---	---	---
Measurements at 240°, in		---	---	---	---
Difference between max and min readings, in:		0° =	0° =	0° =	0° =
		120° =	120° =	120° =	120° =
		Maximum difference must be < 0.0015 in.			
END 2					
Measurements at 0°, in		---	---	---	---
Measurements at 120°, in		---	---	---	---
Measurements at 240°, in		---	---	---	---
Difference between max and min readings, in:		0° =	0° =	0° =	0° =
		120° =	120° =	120° =	120° =
		Maximum difference must be < 0.0015 in.			
		Flatness Tolerance Met?			
		YES			
PERPENDICULARITY					
Maximum Gap Between Square and Top of Specimen, in	0.028	Angle of Departure, °:	0.40	Maximum angle of departure must be < 0.25°	NO
		Perpendicularity Tolerance Met?			
		NO			

Client:	Jacobs Civil, Inc.
Project Name:	BRA/Dudley Square - E2X26200
Project Location:	---
GTX #:	7642
Test Date:	08/10/07
Tested By:	md
Checked By:	jdt
Boring ID:	JE-B1
Sample ID:	RC-1
Depth, ft:	64-69 ft



After cutting and lapping



After break

WARRANTY and LIABILITY

GeoTesting Express (GTX) warrants that all tests it performs are run in general accordance with the specified test procedures and accepted industry practice. GTX will correct or repeat any test that does not comply with this warranty. GTX has no specific knowledge as to conditioning, origin, sampling procedure or intended use of the material.

GTX may report engineering parameters that require us to interpret the test data. Such parameters are determined using accepted engineering procedures. However, GTX does not warrant that these parameters accurately reflect the true engineering properties of the *in situ* material. Responsibility for interpretation and use of the test data and these parameters for engineering and/or construction purposes rests solely with the user and not with GTX or any of its employees.

GTX's liability will be limited to correcting or repeating a test which fails our warranty. GTX's liability for damages to the Purchaser of testing services for any cause whatsoever shall be limited to the amount GTX received for the testing services. GTX will not be liable for any damages, or for any lost benefits or other consequential damages resulting from the use of these test results, even if GTX has been advised of the possibility of such damages. GTX will not be responsible for any liability of the Purchaser to any third party.

Commonly Used Symbols

A	pore pressure parameter for $\Delta\sigma_1 - \Delta\sigma_3$	T	temperature
B	pore pressure parameter for $\Delta\sigma_3$	t	time
CIU	isotropically consolidated undrained triaxial shear test	U, UC	unconfined compression test
CR	compression ratio for one dimensional consolidation	UU, Q	unconsolidated undrained triaxial test
C_c	coefficient of curvature, $(D_{30})^2 / (D_{10} \times D_{60})$	u_a	pore gas pressure
C_u	coefficient of uniformity, D_{60}/D_{10}	u_e	excess pore water pressure
C_c	compression index for one dimensional consolidation	u, u_w	pore water pressure
C_α	coefficient of secondary compression	V	total volume
c_v	coefficient of consolidation	V_g	volume of gas
c	cohesion intercept for total stresses	V_s	volume of solids
c'	cohesion intercept for effective stresses	V_v	volume of voids
D	diameter of specimen	V_w	volume of water
D_{10}	diameter at which 10% of soil is finer	V_o	initial volume
D_{15}	diameter at which 15% of soil is finer	v	velocity
D_{30}	diameter at which 30% of soil is finer	W	total weight
D_{50}	diameter at which 50% of soil is finer	W_s	weight of solids
D_{60}	diameter at which 60% of soil is finer	W_w	weight of water
D_{85}	diameter at which 85% of soil is finer	w	water content
d_{50}	displacement for 50% consolidation	w_c	water content at consolidation
d_{90}	displacement for 90% consolidation	w_f	final water content
d_{100}	displacement for 100% consolidation	w_l	liquid limit
E	Young's modulus	w_n	natural water content
e	void ratio	w_p	plastic limit
e_c	void ratio after consolidation	w_s	shrinkage limit
e_o	initial void ratio	w_o, w_i	initial water content
G	shear modulus	α	slope of q_f versus p_f
G_s	specific gravity of soil particles	α'	slope of q_f versus p_f'
H	height of specimen	γ_t	total unit weight
PI	plasticity index	γ_d	dry unit weight
i	gradient	γ_s	unit weight of solids
K_o	lateral stress ratio for one dimensional strain	γ_w	unit weight of water
k	permeability	ε	strain
LI	Liquidity Index	ε_{vol}	volume strain
m_v	coefficient of volume change	$\varepsilon_h, \varepsilon_v$	horizontal strain, vertical strain
n	porosity	μ	Poisson's ratio, also viscosity
PI	plasticity index	σ	normal stress
P_c	preconsolidation pressure	σ'	effective normal stress
p	$(\sigma_1 + \sigma_3) / 2, (\sigma_v + \sigma_h) / 2$	σ_c, σ'_c	consolidation stress in isotropic stress system
p'	$(\sigma'_1 + \sigma'_3) / 2, (\sigma'_v + \sigma'_h) / 2$	σ_h, σ'_h	horizontal normal stress
p'_c	p' at consolidation	σ_v, σ'_v	vertical normal stress
Q	quantity of flow	σ_1	major principal stress
q	$(\sigma_1 - \sigma_3) / 2$	σ_2	intermediate principal stress
q_f	q at failure	σ_3	minor principal stress
q_o, q_i	initial q	τ	shear stress
q_c	q at consolidation	ϕ	friction angle based on total stresses
S	degree of saturation	ϕ'	friction angle based on effective stresses
SL	shrinkage limit	ϕ'_r	residual friction angle
s_u	undrained shear strength	ϕ_{ult}	ϕ for ultimate strength
T	time factor for consolidation		

Attachment C

Photographs



Approximate Boring Locations on Paved Sidewalk

BRA DUDLEY SQUARE




Approximate Test Pit Location (Retaining Wall Warren Street Side)

BRA DUDLEY SQUARE



Approximate Test Pit and Boring Locations

BRA DUDLEY SQUARE



Approximate Test Pit Location (Basement)

BRA DUDLEY SQUARE

BORING NO	RUN NO	DEPTH	RECOVERY%	RQD	TYPE		
JE-B3	C-1	82'-87'	20"=33%	0"=0%	GRAVEL	JE-B3	E2X26200
JE-B4	C-1	80'-85'	20"=33%	0"=0%	GRAVEL	JE-B4	JAC OBS
JE-B4	C-2	91-96'	20"=33%	0"=0%	CONGLOM		BRA-DUDLEY SQ
JE-B4	C-3	96-101	54"=90%	20"=33%			



Rock Core Box No. 1

JE-B3 Depth = 82-87ft
JE-B4 Depth = 80 - 85ft and 91 - 101ft



Rock Core Box No. 2

JE-B2 Depth = 80-90ft

JE-B1 Depth = 64 - 69ft

BORING NO.	RUN NO.	DEPTH	RECOVERY	RQD	TYPE	E2X26200 JACOBS BRA-DUDLEY SQ	
JE-B3	C-1	82'-87'	20"=33%	0"=0%	GRAVEL	JE-B3	
JE-B4	C-1	80'-85'	20"=33%	0"=0%	GRAVEL	JE-B4	
JE-B4	C-2	91-96'	20"=33%	0"=0%	Gangliah		
JE-B4	C-3	96-101	54"=90%	20"=33%			



Rock Core Box No. 1

JE-B3 Depth = 82-87ft

JE-B4 Depth = 80 - 85ft and 91 - 101ft

BORING ID	RUN NO	DEPTH(ft)	REC. IN. %	RQD IN. %	TYPE
JE-B2	C-1	80-85.0	36"=60%	0"=0%	ARGILLITE
JE-B2	C-2	85.0-90.0	36"=60%	0"=0%	
JE-B1	C-1	64-69.0	60"=100%	12"=20%	CONGLOMERATE

JACOBS
E2X26200
DUDLEY SQUARE
BRA

Rock Core Box No. 2

JE-B2 Depth = 80-90ft


JE-B1 Depth = 64 - 69ft

Environmental Remediation and Building Demolition
At Dudley Square

Geotechnical Report
September 2007



Test Boring and Test Pit Excavation in Progress



Damaged Casing Pipes



Test Pit JE-TP1 Exposed Foundation and Exposed Bottom of Foundation
Retaining Wall at Rear of Building on Warren Street Side



Test Pit JE-TP2 Exposed Foundation and Exposed Bottom of Foundation
Rear of Building



Test Pit JE-TP3 Exposed Foundation and Footing Geometry
Test Pit Excavated in the Basement Front Corner of Building